

  
**ADDENDUM NO. 1**

February 6, 2008  
to  
Plans, Specifications And Contract Documents  
for the  
Airport Clearing and Grubbing Project  
at the  
Newberry County Airport  
Newberry, South Carolina  
FAA AIP No. 3-45-0066-06  
WKD No.: 50273.10.CA

Bidders and other interested parties are informed that the above referenced plans, specifications and contract documents are hereby revised, changed and supplemented as set forth below:

Specifications:

1. Section – P-159, Rip Rap: Under “Method of Measurement” replace Section 159-4.1 with the following:

**“The quantity of rip rap outlet protection to be paid for will be the actual number per each of rip rap outlet protection, measured in place and accepted.”**

2. Section – P-159, Rip Rap: Under “Basis of Payment”, in Section 159-5.1 delete the first paragraph and replace it with the following:

**“The payment of the rip rap outlet protection will be at the bid price per each. All work to place the rip rap outlet protection shall be in the bid price and will include all materials, equipment, labor and incidentals (including filter fabric) to accomplish the job in an acceptable manner.”**

Plans:

1. Sheet 7, Erosion and Sediment Control and Miscellaneous Construction Details: The precast structure with extended base slab in the Converted Sediment Trap Pond #2 Outlet Structure Detail shall have a 4’ inside square dimension with 6” thick walls.
2. Sheet 8, Erosion and Sediment Control and Miscellaneous Construction Details: The precast structure with extended base slab in the Converted Sediment Trap Pond #1 Outlet Structure Detail shall have a 4’ inside square dimension with 6” thick walls.