

Questions for Dillinger Road Widening and Paving Project

Several questions were asked and answered at the pre-bid meeting. Answers to the following questions which were not resolved at the meeting are now provided:

QUESTION 1:

Will a SCDHEC land disturbance permit be required for this work?

Yes. Newberry County is in the process of obtaining the required permit.

QUESTION 2:

What is the required interval for compaction testing?

Compaction must be verified by a certified lab in writing. The lab shall determine random intervals for testing of the base layer, but in any case, the interval must not exceed five-hundred feet (500'). Lab testing shall include verification of the base layer thickness as well as compaction. In addition, contractor shall provide the County copies of all delivery tickets for aggregate delivered to the site.

Questions submitted since pre-bid meeting

QUESTION 3:

Are all concrete pipes including sidelines to be 18" in diameter? Typically sideline (driveway pipes) are 15".

Fifteen inch (15") driveway pipes are acceptable for ditches that are comparably sized, however, larger ditches may require larger driveway pipes to facilitate proper drainage.

QUESTION 4:

Is there to be rip-rap placed around both inlet and outlet of cross line pipes?

Yes.